



SECTION THROUGH CHAMBER WALL

NOTE

1. CONDUITS TO BE ENCASED IN 150mm OF CONCRETE FOR A DISTANCE OF 1500mm BEYOND EXTERNAL WALL OR PAVED AREA AND TO FINISH 750mm BELOW GROUND LEVEL
2. EXCESS CONDUIT IS TO BE CUT OFF FLUSH WITH THE WALL AND EDGES GROUND SMOOTH
3. DIMENSIONS ARE TO BE INDICATED ON THE REQUIREMENTS DRAWING SHOWING THE PROPOSED LOCATION.
4. ALL JOINTS ARE TO BE SEALED AND WATERPROOF
5. ON COMPLETION OF INSTALLATION CONDUITS ARE TO BE CLEANED AND FITTED WITH CLOSE FITTING SEALING PLUGS
6. AFTER INSTALLATION OF CABLES DUCTS ARE TO BE SEALED

NOT TO SCALE

					The information contained within this drawing & associated electronic file shall remain the property of Evoenergy and shall not be copied or used for any other purpose without express written permission from Evoenergy. © Evoenergy. 2018. ACT Cadastral information supplied by the ACT Environment & Sustainable Development Directorate. © ACT Gov. 2018.
C	LOGO AND REFERENCES UPDATED	18/03/2018	B. Suthar	W. Ibrahim	
B	LOGO UPDATED	27/03/2008	AC	GA	
No	Revision	Date	Checked	Approved	

<p>HIGH LEVEL HV CABLE CONDUIT ENTRY TO CHAMBER SUBSTATION STANDARD CONFIGURATION</p>		Drawn:	S.Read	Date:	16/01/1996	
		Designed:	E. Amaratunga			
		Checked:	M. Charlton			
		Approved:	A-NNR			
Project No:	Status: Current	A4	4931-07	C		
Work Pack No:	File:					